प्रारंभिक व्यावसायिक परीक्षण रिपोर्ट संख्या/No. CSIR/CMERI/FMTTC/2023/015

INITIAL COMMERCIAL TEST REPORT #16/Month: August, 2023

THIS TEST REPORT VALID UP TO : 31st AUGUST, 2030



# PSD MS POWER MAIZE SHELLER



कृषि मशीनरी प्रशिक्षण और परीक्षण केंद्र
Farm Machinery Training and Testing Centre
सीएसआईआर- केन्द्रीय यांत्रिक अभियांत्रिकी अनुसंधान संस्थान

CSIR - Central Mechanical Engineering Research Institute

महात्मा गांधी एवेन्यू, दुर्गापुर

Mahatma Gandhi Avenue, Durgapur

पश्चिम बंगाल - 713209

West Bengal - 713209 Website: https://cmeri.res.in

E-mail: fmttc.cmeri@gmail.com Telephone: +91-343-2546749; 9434921623

Fax: +91-343-2546745

CSIR/CMERI/FMTTC/2023/015

#### PSD MS POWER MAIZE SHELLER (INITIAL COMMERCIAL TEST)

Name & Address of Applicant

: PSD INDUSTRIES PVT. LTD UG-9, Shree Ram Plaza,

Station Road, Patna - 800001 (Bihar)

Test Conducted at

 Farm Machinery Training and Testing Centre CSIR- Central Mechanical Engineering Research Institute, M G Avenue, Durgapur, Pin – 713209, West Bengal.

#### THIS TEST REPORT VALID UP TO: 31/08/2030

[vide DAC&FW OM No. 13-24/2018 - M&T (I&P) dated 19.09.2018]





Report No.: CSIR/CMERI/FMTTC/2023/015

Month: August Year: 2023

CSIR - Central Mechanical Engineering Research Institute, Durgapur - 713209 (W.B.), INDIA

Farm Machinery Training and Testing Centre.
CSIR-Central Mechanical Engineering Research Institute, Durgapur
THIS REPORT IS VALID UPTO: 31st AUGUST 2036

2 of 18



#### PSD MS POWER MAIZE SHELLER (INITIAL COMMERCIAL TEST)

Table -5 Data Sheet for TEST at LOAD

Item	1	2	3
Source of Power	Electric Motor		
Power rating (kw)	0.9	0.9	0.9
Type of Drive	3	Belt and Pulley	7
Variety of Maze		Parjenta 7744	
Grain to cub ratio	87.41	89.41	87.98
Moisture content	13.72	12.52	13.51
Concave clearance (mm)	27.11 to 40	27.11 to 40	27.11 to 40
Atmospheric Temp (°C)	32	31	36
Humidity (%)	86	98	69
Atmospheric pressure (mm of Hg)	74.26	68.26	51.75

Table - 6 Data Sheet for LOSSES, EFFIICENCY AND CAPACITY

SI.	Items	Calculation	Test number		
No.			1	2	3
а	Shelling unit speed (RPM)	Direct Measurement	1632,00	1639.00	1580.00
ь	Feed rate (kg/h)	Direct Measurement	624.00	640.80	610.80
c	Grain content in cub	Manual shelling of sample	0.87	0.89	0.88
d	Total grain output in feed (kg)	bxc	545.43	572.95	537.41
e	Total grain output at grain outlet (kg/h)	Direct Measurement	531.96	547.20	526.08
f Total unshelled grain (Kg)		Sample analysis	0.15	0.10	0.21
g Percent of unshelled grain (%)		100 x f/d	0.03	0.02	0.04
h Blown grain in husk outlet (Kg)		Sample analysis	NA.	NA	NA
i	Blown grain in husk outlet (%)	100 x h/d	NA	NA	NA
i	Total cracked and broken grain (kg)	Sample analysis	0.34	0.26	0.21
k	Percent of cracked and broken grain (%)	100 x j/e	0.06	0.05	0.04
1	Shelling efficiency (%)	100 - g	99.97	99.98	99.96
m	Total loss (%)	g+i+k	0.09	0.07	0.08

Farm Machinery Training and Testing Centre, CSIR-Central Mechanical Engineering Research Institute, Durgapur THIS REPORT IS VALID UPTO: 31st AUGUST 2030

Mile then

12 of 18

# CSIR/CMERI/FMTTC/2023/015

#### PSD MS POWER MAIZE SHELLER (INITIAL COMMERCIAL TEST)

n	Power rating (Kw)	Direct Measurement	0.90	0.90	0.90
0	Output Performance (Kg/Kwh)	e/n	591.07	608.00	584.53

Table - 7 Corrected Output Capacity

a	Feed rate (Kg/h)		624.00	640.80	610.80
b	Output Capacity (Kg/h)		531.96	547.20	526.08
c	Observed moisture content (%)		13.72	12.52	13.51
d	Observed grain ratio (%)		87.41	89.41	87,98
e	Corrected Output Capacity (Kg/h)	b-((b(c- 12)/88)40)/d	238.68	243.35	235.06
f	COC % with feed rate		38.25	37.98	38.48

## Table - 8 Corrected Output Capacity

SI. No.	Clause 8.2 of IS 7052 : 1973 (reaffirmed 2012)	As observed
1	Total running time, h	28
2	Continuous running time, h	.3
3	Breakdowns in shelling unit	No
4	Breakdown in cleaning unit	NA
5	Breakdowns in elevating unit	NA.
6	Breakdown in body	No
7	Any major repair conducted	No

#### 7 Defects, Breakdown and repair

No defects and breakdowns of the machine were observed during the period of test.

### Observations:

St. No.	Observations as per IS 7052:1973 (reaffirmed 2012) clause 8.1.4.5 and 8.1.4.6	As observed
4.1	Presence of any marked oscillation during operation	No
4.2	Presence of undue knocking or rattling sound	No
4.3	Frequent slippage of belts	No
4.4	Smooth running of shafts in their respective bearings	Yes
4.5	Frequent clogging of shelling units	No
4.6	Frequent clogging of sieve aperture	No
4.7	Smooth flowing of material through different components	No
4.8	Vibration free running of fan	NA
4.9	Frequent clogging of grain in elevator unit	No
4.10	Any marked rise in bearing temperature	No

Farm Machinery Training and Testing Centre, CSIR-Central Mechanical Engineering Research Institute, Durgapur THIS REPORT IS VALID UPTO: 31st AUGUST 2030

13 of 18



CUB-CHELL

### PSD MS POWER MAIZE SHELLER (INITIAL COMMERCIAL TEST)

#### 11 TECHNICAL LITERATURE

The operator, maintenance & parts manual of maize sheller was provided during the test which was found adequate, however, the manual should be updated as per IS: 8132:1999, with the inclusion of safety instructions regarding handling of machine.

#### TESTING AUTHORITY

Report Prepared by	Sr. Technical Officer, CSIR-CMERI Farm Machinery Testing Centre	Jel-10/2023
Report Verified by	Scientist, CSIR-CMERI Farm Machinery Testing Centre	Thurs of the 3
Report Approved by	In-Charge, CSIR-CMERI Farm Machinery Testing Centre	Subreta la Mandel 10/8/2023
Report Approved for release by	Head, Business Innovation and Skill Group, CSIR-CMERI, Durgapur	Ludif Samta

#### 12 APPLICANT'S COMMENTS

Para No.	Our Reference	Applicant's Comments
12	10.1 - 10.5	Noted and will be rectify as per your recommendation



