

Name of work : Fixing of pipe line connection to the newly installed Water Tanks in quaters in P row,
N row, M row, L row and K row in CMERI colony, Durgapur

SCHEDULE

Item. No.	Description of work	Unit	Total qty considered	rate (rs)	Amount (Rs.)
1	Labour for fitting and fixing G.I. pipes above ground (exposed) in structures with holder bat clamps including cost of jointing materials, holder bat clamps etc.,as necessary, including cutting pipe, making threads etc. complete in all respect with two coats of painting with approved paint any height. (Payment will be made on the centre line measurement of the total pipeline including specials. Payment of painting will be paid seperately). 20 mm dia	Mtr.	75		
2	Labour for fitting and fixing G.I. pipes above ground (exposed) in structures with holder bat clamps including cost of jointing materials, holder bat clamps etc.,as necessary, including cutting pipe, making threads etc. complete in all respect with two coats of painting with approved paint any height. (Payment will be made on the centre line measurement of the total pipeline including specials. Payment of painting will be paid seperately). 25 mm dia	Mtr.	12		
3	Supply of G. I. pipes of TATA make including necessary sockets/ reducing sockets. (b) 20 mm dia. ii) Medium quality	Mtr.	50		
4	Supply of G. I. pipes of TATA make including necessary sockets/ reducing sockets. (b) 25 mm dia. ii) Medium quality	Mtr.	6		
5	Supply of G.I. plain tee of approved brand and make. (ii) 20 mm	each	48		
6	Supply of G.I. plain tee of approved brand and make.(iii) 25 mm	each	6		
7	Supply of G.I. reducing tee of approved brand and make. (iii) 25 mm X 20 mm	each	26		
8	Supply of G.I. reducing tee of approved brand and make. (viii) 40 mm x 20mm	each	4		
9	Supply of G.I. union. (ii) 20 mm	each	100		

Name of work : Fixing of pipe line connection to the newly installed Water Tanks in quaters in P row, N row, M row, L row and K row in CMERI colony, Durgapur

SCHEDULE

Item. No.	Description of work	Unit	Total qty considered	rate (rs)	Amount (Rs.)
10	Supply of G.I. union. (iii) 25 mm	each	30		
11	Supply of G.I. plain equal elbow of approved brand and make. 20 mm	each	10		
12	Supply of G.I. reducing elbow. (iii) 25 mm X 20 mm	each	10		
13	Supply of G.I. reducing elbow. (viii) 40 mm x 20mm	each	4		
14	Supply of G.I. short piece of TATA make (from 50mm & upto 150 mm long). (ii) 20mm	each	200		
15	Supply of G.I. short piece of TATA make (from 50mm & upto 150 mm long). (iii) 25 mm	each	48		
16	Supplying, fitting and fixing gunmetal wheel valve of approved brand and make tested to 21 kg per sq. cm. (for water lines only) . 20 mm dia.	each	2		

TOTAL

* Supply of materials shall be as per the requirement of the execution of the work. Excess manterials after the work, if any shall be returned to the contractor.

Shubha
20/02/19